

Clear Span Aluminum Party Marquee Tents Designed for Croatian Island Celebration Venues

Our Product Introduction

Basic Information

- Place of Origin: Guangdong, China
- Brand Name: Tendars
- Certification: CE, ISO 9001, EN 13782, DIN 4102 B1 fabric
- Model Number: TD-PMT-02
- Minimum Order Quantity: 1 set
- Price: USD 25 - 95 per square meter
- Packaging Details: Frame in bundles by assembly order, fabric folded with interleaving, fittings in labelled crates
- Delivery Time: 15-25 working days after drawing confirmation
- Payment Terms: T/T 30% deposit, balance before shipment; L/C at sight
- Supply Ability: 12000 square meters per month



Product Specification

- Frame Material: Hard-pressed Extruded Aluminum 6061/T6
- Frame Profile: 64 / 82 / 100 / 120 Mm Series By Span
- Roof Fabric: 650-850 G/sqm Double PVC-coated Polyester
- Side Wall: PVC, Clear PVC, Glass Panel, Mesh, ABS Hard Wall
- Wind Load: Engineered Configuration With Written Operating Limits
- Snow Load: Steeper Pitch And Reduced Purlin Spacing Options
- Fire Retardant: DIN 4102 B1 / EN 13501 B-s1,d0 On Request
- Application: Island Celebration Venues
- Warranty: 5 Years Frame, 2 Years Fabric
- Service: Shop Drawings, Supervisor Installation, Lifetime Spares
- Highlight: **Clear Span Aluminum Party Marquee Tents**,



More Images



for more products please visit us on marquees-tent.com



Our Product Introduction

for more products please visit us on marquees-tent.com

Product Description

On an island venue, every square metre of usable floor is expensive. Ferries limit what can be delivered, storage space is scarce, and the building itself is often protected, so the event has to fit into a courtyard or terrace with no room for interior columns. A clear span aluminum party marquee tent solves that geometry problem: the entire interior is free of posts, so seating plans, stages and buffets can be laid out around the guest experience rather than around structural obstacles.

The frame carries load through the roof beams and down the perimeter legs, which means the span is limited only by the profile series selected, not by internal supports. For island resorts in Brac, Korcula or the Kornati area, this also simplifies logistics: components are nested and palletised, fit into a standard container, and can be transferred to the site by a small ferry or a single flatbed truck.

Key Features and Selling Points

- **Column-free interior:** Load is transferred through roof beams to perimeter legs, leaving the whole floor available for tables, stages, dance floors and buffet lines.
- **Ferry-friendly packing:** Beams, legs and purlins are nested into compact bundles that fit standard containers and small island ferries without special permits.
- **Modular bay lengths:** Bays can be added or removed on site, so a venue can start with a ceremony layout and extend for dinner without a second structure.
- **High eave clearance:** Generous eave height keeps the space cool, allows tall floral installations and stage rigging, and improves airflow during summer events.
- **Integrated rigging points:** Pre-drilled beam nodes accept lighting bars, speaker mounts and projection screens without drilling the frame on site.
- **Island-ready anchorage:** Ballast, stake and anchor-bolt base options cover stone courtyards, gravel and hard rock ground conditions.

Technical Specifications

Parameter	Specification
Structural type	Clear span, no internal columns
Span range	Multiple profile series, wide spans available on request
Rigging capacity	Designated beam nodes for lighting and AV loads
Delivery format	Nested bundles, container compatible
Frame material	Hard-pressed extruded aluminum alloy 6061/T6, anodized finish
Frame profile series	64 mm / 82 mm / 100 mm / 120 mm square profiles by span
Bay spacing	3 m / 4 m / 5 m modular bays, extendable at any time
Eave height options	2.5 m to 4 m clear height, higher on request
Roof fabric	650 g / 750 g / 850 g per sqm double PVC-coated polyester, blackout available
Side wall options	Solid PVC, clear PVC, glass panel, mesh, glass door, ABS hard wall
Fire performance	Fabric meeting DIN 4102 B1 / EN 13501 B-s1,d0 on request
Wind load guidance	Engineered configuration by site exposure, documented operating limits
Snow load guidance	Steeper pitch and reduced purlin spacing for snow regions
Temperature range	-30 C to +70 C service range for fabric and frame
Design life	15 years frame, 8 to 10 years fabric under normal use
Warranty	5 years on aluminum frame structure, 2 years on PVC fabric

All values are configuration dependent. Final specifications are confirmed on the approved drawing before production.

Configuration Guide for Croatian Buyers

Use the table below to match the structure to your site exposure and event type. Our engineers confirm the final configuration against

photographs of the ground, the prevailing wind direction and the event duration.

Duty level	Typical use	Recommended build
Light duty	Garden parties, short events, sheltered inland sites	64 mm profile, alternate bay bracing
Standard duty	Weddings, corporate functions, coastal towns in summer	82 mm profile, cross-braced bays, mixed walls
Heavy duty	Exposed coast, island venues, public events, winter use	100-120 mm profile, full bracing, engineered anchors

Applications

Island venues use this tent for wedding receptions, anniversary galas, wine tasting evenings, small music events and hotel guest dinners. It is equally useful on the mainland where a heritage courtyard cannot take internal posts. Because the interior is unobstructed, caterers can run straight buffet lines, planners can place a long top table anywhere, and photographers get clean sightlines to the sea without a post cutting through the frame.

Logistics Planning for Island Deliveries

Island projects succeed or fail on logistics. We prepare a packing list by bay so the crew knows exactly which bundle goes up first, and we label every crate with its position in the assembly sequence. When a ferry booking limits vehicle length, the shipment can be split across two crossings without confusing the build, because the first delivery always contains the frame and roof needed to close the structure against weather.

We also advise on crew size. A clear span structure is heavier per component than a small pagoda, so we recommend a minimum of six installers for larger spans and confirm lifting equipment availability in advance. For venues without a forklift, we supply a simple A-frame lifting bar that lets four people raise a beam safely on uneven island ground.

Why Croatian Event Buyers Work With Tendars

Every project starts with an engineering question rather than a catalogue page: what wind will this structure see, what ground will it stand on, and how long will it stay up. Our technical team reviews site photographs, exposure and event duration before a configuration is proposed, and the recommendation is issued as a drawing set that a venue manager or a safety officer can actually read.

The factory behind that advice is vertically integrated. Aluminum profiles are cut, machined and welded in house, PVC panels are welded on our own high-frequency lines, and every frame is trial assembled before it is packed. Because we control both the metal and the membrane, a buyer gets one supplier responsible for fit, tension and finish instead of two parties pointing at each other when a panel does not line up.

Documentation is part of the product. Shipments include shop drawings, the packing list matched to crate labels, an installation sequence and a maintenance sheet, and we retain the drawings so that repeat orders match the first delivery exactly. For public events, hotel terraces and protected sites we also prepare the fire performance and anchoring paperwork that local inspections typically request.

Notes for the Croatian Market

Most Croatian event enquiries arrive with three requirements: the structure must look right for a coastal or heritage setting, it must stand up to wind that arrives without warning, and it must be installed inside a tight access window. We address these in the quotation stage rather than after the order, which is why our proposals include anchoring options, installation crew guidance and a delivery sequence suited to ferry timetables and old town access restrictions.

Documentation matters too. Public events, hotel terraces and protected sites increasingly require fire performance evidence and a clear anchoring plan. We prepare those documents with the order so the organiser can answer a venue or an inspection without delay, and we keep the drawings on file for repeat orders so the second season is faster than the first. For island celebration venues, that translates into a specification we confirm on the drawing, a delivered price to the Croatian port and a build sequence the local crew can follow without supervision.

Frequently Asked Questions

- **How is wind resistance confirmed for a specific site?** We review photographs of the ground, surrounding buildings and prevailing wind direction, then issue a configuration with written operating limits. Where a site is fully exposed we specify heavier profiles, continuous bracing and anchoring suited to rock or thin soil instead of garden stakes.
- **Which documents come with the shipment?** Shop drawings, a packing list matched to crate labels, an installation sequence, a maintenance sheet and, where required, fabric fire certification and test reports. These are the documents venues and inspections normally ask for, so they travel with the goods rather than arriving later.
- **Can one frame be used for summer and winter events?** Yes. The frame is the durable part, so we supply interchangeable skins: open or mesh walls with a shade roof for summer, solid insulated walls with liners and heating ports for winter. Storage is then limited to the panels not currently in use.

Packaging and Quality Assurance

Packing follows the build sequence rather than the shape of the components: the frame and roof bundle that closes the structure against weather is loaded last so it can be unloaded first. Fabric panels travel folded with interleaving to prevent abrasion in transit, and fittings are boxed by assembly stage so nothing has to be sorted on site.

Each crate is weighed, labelled and photographed before loading, and the photographs are sent with the shipping documents. That record settles most transit questions quickly and tells the receiving crew exactly what should be on the pallet before they sign for it.

Request a Quotation

Send us your site location, expected guest numbers, event dates and ground surface, and we will return a configuration proposal with anchoring options, installation guidance and a delivered price to your Croatian port or site. Samples of fabric and frame profiles can be couriered on request.

Email: amanda@marquees-tent.com | WhatsApp: +86-13640286461 | Web: http://www.marquees-tent.com

Guangzhou Tendars Tent Co., Limited

0086 13640286461 amanda@marquees-tent.com marquees-tent.com

No.319, 2nd building , 8th zone , Aoyuan city plaza , Zhongcun Street, Guangzhou, Guangdong, China